

## Constellation-X FST Meeting

# Kent Irwin (NIST)

#### Columbia University, May 2003

- $\rightarrow$  2x10 MUX test ADR
- → Multiplexing 8 microcalorimeters
- → Surface-micromachined arrays
- → Noise reduction with new pixel geometries

#### The NIST Team

Kent Irwin

James Beall

Anna Clark

Steve Deiker

Randy Doriese

Lisa Ferreira

Gene Hilton

Carl Reintsema

Joel Ullom

Leila Vale

Yizi Xu

Barry Zink


Martin Huber - CU Denver







## 2x10 Multiplexed Test Facility

8×8 μcal array filter chip MUX chip













# Multiplexing 8 microcalorimeters

- $\rightarrow$ 8 µcalorimeters multiplexed in our "2 × 10" test facility from one 8 × 8 microcalorimeter array.
- → Tests were done with Joule heating pulses. X-ray tests are now underway.
- → No statistically significant degradation in energy resolution was seen for 8 multiplexed pixels.
  - 6.4 +- 0.2 eV for 2 pixels
  - 6.7 +- 0.2 eV for 4 pixels
  - 6.7 +- 0.2 eV for 8 pixels
- $\rightarrow$  Inductive filter limited risetime to  $\sim$  35  $\mu$ s. Compatible with response time >= 200  $\mu$ s.









### Performance target for multiplexer

For Constellation-X, significant improvements in amplifier / MUX performance are targeted to achieve 32 pixels multiplexed per output channel:

- Individual SQUID noise improved from 0.5  $\mu\Phi_0/\sqrt{\text{Hz}}$  to ~ 0.1  $\mu\Phi_0/\sqrt{\text{Hz}}$ .
- Open-loop bandwidth of the amplifier chain increased from ~ 3 MHz to ~12 MHz.
- Algorithms to robustly correct for photon arrival time.


#### Status:

- SQUIDs demonstrated with 0.15  $\mu\Phi_0/\sqrt{Hz}$  white-noise level.
- New designs for SQUID MUX chip, wiring to 4 K, and 300 K preamp now underway.
- Algorithms are being tested.



### Surface-micromachined µcal arrays


- More room for wiring vs. bulk micromachining, wafers more robust.
- New "platform" design vs. old "table leg" design – improved pixel yield
- ~100% yield on pixels without absorbers
- Some pixels with Bi absorbers still fail on cooling



SEM image of "platform" design





Table legs













8×8 array of TES microcalorimeters with 2 μm Bi absorbers




### Dependence of Detector Noise on Geometry

- measure 20 sensors per thermal cycle in multiplexed "2×10" test facility
  - greatly expanded testing throughput
- have fabricated devices with various geometries:
  - wedges, normal bars, normal islands, ...








engineer superconducting-normal phase boundary less noise?





#### **Demonstrated Noise Reduction**

choose operating point to <u>maximize</u> excess high-frequency noise



- Measurements ongoing
- Some designs have no effect (incl. normal islands)
- Some designs (incl.
  perpendicular bars) greatly
  reduce noise, but also reduce α
- Some designs (incl. wedges) modestly reduce noise with little effect on  $\alpha$
- Effect on energy resolution? X-ray tests of promising designs underway.

significant noise reduction possible



- Multiplexing with x-ray signals culminating in "2x8" demo.
- Development of next-generation MUX system, including low-noise and high-bandwidth SQUIDs and room-temperature electronics.
- Optimization of surface-micromachined arrays for robustness, and demonstration of array with Constellation-X form factor and efficiency.
- X-ray illumination of microcalorimeters with new geometries, tests of additional designs, studies of noise mechanisms, and optimization of single pixel for Constellation-X.